



STS-102/ET-107 Flight Readiness Review

External Tank Project







Overview

LMSSC/ET - Gale Copeland

Date February 27, 2001

Presenter

Page 2

Limited Life Component Status

- All items within required life
- Processing Anomalies None
- Design Change
 - Resize foam thickness on LO2 tank ogive
- Waiver Status
 - LO2 tank TPS does not meet the launch probability "no-ice" requirement
 - Presented with *Design Change*
 - LH2 feedline contamination
- Open work/paper No constraints





Daniero Ob

Design Change Resize Foam Thickness on LO2 Tank Ogive

Presenter LMSSC/ET - Gale Copeland	
Date February 27, 2001	Page 3

Change

- Resized foam thickness on LO2 tank ogive
 - Decreased minimum net sprayed foam thickness on the +Z LO2 tank

 LO2 Tank 	STS-98/ET-106	STS-102/ET-107	
Station 404	2.15 <u>+</u> 0.25	1.85 <u>+</u> 0.25	
to	↓	↓	
Station 540	2.15 <u>+</u> 0.25	1.00 <u>+</u> 0.15	
Station 570 - 848	1.00 <u>+</u> 0.15	0.88 <u>+</u> 0.13	

Background

- Producibility
 - Eliminate TPS rework (sanding) effort associated with potential negative contour deviations on the +Z LO2 tank adjacent to the Station 536 O2 weld
 - Contour deviations could, if not addressed, cause TPS cracking during tanking resulting in scrub or TPS debris



Reworked (sanded) area at Station 536

(STS-95/ET-98 shown)






Design Change
Resize Foam Thickness on LO2 Tank Ogive

Prese	^{nter} LMSSC/ET - Gale	Cope	land
Date	February 27, 2001	Page 4	4

- Waiver as result of foam thickness reduction
 - Subsequent thermal analysis showed that thickness reduction resulted in an inability to meet the launch probability requirement of NSTS 07700, Vol. X, para 3.2.1.2.14
 - Launch holds due to ice formation shall not occur more than 5% of the time on annual basis
 - Reduced foam thickness results in a minor decrease in launch probability (93.3% vs 95% required)
 - Waiver to NSTS 07700, Vol. X, para 3.2.1.2.14 approved for ET-102 & ETs 107-110 (PRCBD S071290, 03/10/00)
 - Previously presented for STS-101/ET-102







Design Change Resize Foam Thickness on LO2 Tank Ogive

Presenter LMSS		nter LMSSC/ET - Gale	e Copeland
	Date	February 27, 2001	Page 5

- Basis for Certification
 - Analysis
 - Structural:
 - No change to ascent temperatures/FS unchanged
 - · Reentry requirements maintained
 - Propulsion: LO2 mass requirement maintained
 - · Negligible impact due to heat gain
 - Aero: No impact to surface waviness
 - Inspection Final Inspection Team routinely monitors the External Tank for ice formation that would violate a Launch Commit Criteria (LCC)
 - If ice formation were predicted prelaunch, the final inspection team walkdown would initiate an assessment using the tools defined in the LCC to determine if ice is present





Waiver Status

Prese	nter LMSSC/ET - Gale	Copeland
Date	February 27, 2001	Page 6

- LO2 tank TPS does not meet the launch probability "no-ice" requirement
 - Waiver to NSTS 07700, Vol. X approved on 03/10/00, PRCBD S071290
 - Previously discussed with Design Change

LH2 feedline contamination

- During a routine borescope inspection of the ET-107 LH2 tank feedline system, two pieces of material were observed that exceeded the 400 micron level requirement in SE-S-0073, Specification Fluid Procurement and Use Control and ICD 2-12001 (Orbiter Vehicle)
 - 0.375" long x 0.003" diameter raised metallic burr on the cruciform
 - 0.212" long x 0.053" wide cloth fiber
 - Both particles were discovered downstream of the LH2 tank siphon screens
- After coordination with the MPS and the SSME community, it was determined that this contamination issue poses no safety-of-flight concern
 - No compatibility issue with either object
 - MPS can tolerate the ingestion of these particles with no deleterious effect on performance
- Waiver to SE-S-0073 and ICD 2-12001 approved on 01/23/01, PRCBD S058410H





Readiness Statement

Presenter LMSSC/ET - Gale Copeland

Date February 27, 2001 Page 7

The External Tank, ET-107, is certified and ready for STS-102 flight pending completion/closure of open and planned work